



Clallam County Public Works Department

223 E. Fourth St., Suite 6
Port Angeles, WA 98362-3015

FACSIMILE TRANSMITTAL

Date: 05/10/07
To: Bidders and Planholders of the
Elwha River Bridge Replacement Project
From: Clallam County Public Works Department
Subject: Addendum No. One (1)

Total number of pages 4 (including this page).

Comments:

Please acknowledge receipt of this fax, **whether or not you intend to enter a bid**, either by filling in the space provided below and faxing this page to (360) 417-2513 or by calling (360) 417-2319. Acknowledgement of the Addendum on the signature sheet of the Proposal is still required. Thank you for your assistance.

Company Name (please print)

Signature

Date



Clallam County Public Works Department

223 E. Fourth St., Suite 6
Port Angeles, WA 98362-3015

DATE: May 10, 2007

ATTENTION: ALL BIDDERS AND PLANHOLDERS

Elwha River Bridge Replacement Project CRP C1190
Federal Aid Project Number BROS-2005(015)
Federal Aid Contract Number LA-2374

ADDENDUM NO. ONE (1)

You are hereby notified of the following changes in the plans and specifications for the above referenced project.

Item No. 1

The First paragraph of the Notice of invitation for Bids is replaced with the following:

“SEALED BIDS will be received by the Board of Clallam County Commissioners at 223 East Fourth Street, Room 150, Port Angeles, Washington until 10:00 a.m., Tuesday, **June 5, 2007**, at which time they will be publicly opened and read aloud for: “

Item No. 2

Add the following Special Provision to the Contract Documents:

1-02 BID PROCEDURES AND CONDITIONS

1-02.1 Prequalification of Bidders

Delete this Section and replace it with the following:

1-02.1 Qualifications of Bidder

(October 1, 2005 APWA GSP)

Bidders shall be qualified by experience, financing, equipment, and organization to do the work called for in the Contract Documents. The Contracting Agency reserves the right to take whatever action it deems necessary to ascertain the ability of the bidder to perform the work satisfactorily.

Item No. 3

Items 2, 12, 14, and 15 of the Special Provision Titled Environmental Regulations are replaced with the following:

2. Work below the Ordinary High Water Mark (OHWM) on the Elwha River must only occur between July 15 and **September 21** of 2007 and 2008.

12. Material for the gravel pad shall be consisting of granular material, either naturally occurring or processed, and shall meet the following requirements for grading and quality. All percentages are by weight:

Sieve Size	Percent Passing
6" square	100
3" square	75-100
U.S. Number 40	50 max.
U.S. Number 200	2 max.
Sand Equivalent	30 min.

14. During marbled murrelet nesting season (March 1 through August 15), a cumulative noise level (including background noise) above **70db** within the work area, shall not occur during the following periods: from sunrise until 2 hours after sunrise and from 2 hours before sunset until sunset. The noise level shall be measured by the contractor using an approved meter to assure compliance whenever work occurs within the aforementioned periods.

This restriction shall not apply to work associated with the culvert and ravine crossing for the construction access road or any part of the construction access road located east of the east rim of the Elwha River canyon.

15. Deleted (see item 12)

Item No. 4

The Special Provision titled "Time for Completion" is changed to read

Time For Completion

(April 3, 2006)

Section 1-08.5 is supplemented with the following:

This project shall be physically completed within 450 working days.

Contract time shall begin on the latter of: the first working day following the 21st calendar day after the date the Contracting Agency executes the contract or the first day the Contractor starts onsite work. In no case shall the beginning of contract time be later than August 15, 2007.

Item No. 5

In the Special Provision titled "Cooperation with Other Contractors", the fifth sentence of the Second paragraph of the Elwha River Restoration Project Section is changed to read "This will require maintaining a minimum twelve foot wide drivable access to Sampson Road, at the SW corner of the bridge, throughout construction, EXCEPT that access will not be required to be maintained during 2007".

Item No. 6

Federal Wage Rates were amended on 04/27/07.

Pages 1 – 48 are deleted and replaced with Pages 1 – 48. (WA070001 Modification 7 04/27/07)

The federal wage rates included in this contract have changed to Modification No. 7

Item No. 7

In the bid proposal, the bid items in Schedule A titled, “**Archaeological and Historical Salvage**” and “**Field Office Building**” are renumbered as bid items 79 and 80 respectively.

Item No. 8

On Plan Sheet C-6, the note “CROWN Z WATER RD (NOT TO BE USED FOR HEAVY EQUIPMENT)” is revised to read “Crown Z Water Rd shall not be used for heavy equipment except for construction and/or removal of the gravel pad utilized for Method 1 Bridge Removal. For the gravel pad construction and/or removal loads running on Crown Z Water Road shall be limited to the minimum necessary, but in no case shall exceed 20 tons without prior approval of the Engineer.”


Item No. 9

Item 1 of General Note 8 on Sheet S-3, is revised to read “Unbalanced dead load due to segment construction sequence as shown on plans.”

Item No. 10

The reference to August 31 in Note 4 on Plan Sheet S-4, is changed to “September 21”.

All bidders will be required to furnish the Clallam County Engineer with evidence of receipt of this addendum, as provided for on the proposal signature sheet. This addendum will be incorporated in and made part of the contract when awarded and when formally executed.



ROSS TYLER, P.E.
Clallam County Engineer